

LEGEND AND SET UP KIT.


VTR - VENT THRU ROOF
 MV - MECHANICAL VENT

- 40(3) -3" PIPE
- 10(2) -2" PIPE
- 0(1) -1 1/2" PIPE
- 0 A -3"X2" REDUCER
- 0 B -3"X1 1/2" REDUCER
- 2 C -3" ELTL 90°
- 0 D -3" ELL 45°
- 3 E -3" LTTY
- 3 F -3" COUPLING
- 0 G -3" X 3" X 3" X 2" X 2" ST
- 0 H -3" X 3" X 2" X 2" ST
- 0 I -3" X 3" X 2" ST
- 0 J -3" 3 WAY ELL
- 0 K -2"X1 1/2" REDUCER
- 1 L -2" ELTL 90°
- 0 M -2" ELL 45°
- 0 N -2" LTTY
- 1 O -2" COUPLING
- 0 P -2" X 1 1/2" X 1 1/2" ST
- 0 Q -2" 3 WAY ELL
- 0 R -1 1/2" ELTL 90°
- 0 S -1 1/2" ELL 45°
- 0 T -1 1/2" LTTY
- 0 U -1 1/2" COUPLING
- 0 V -1 1/2" CLEAN OUT
- 0 W -1 1/2" SAN TEE

APPROVED  **APPROVED**
 12 JUN 2023
 Federal Manufactured
 Home Construction
 And Safety Standards

3

GILES HOMES	Model #: MODEL#	Drawing #:
405 S. BROAD ST. NEW TAZEWELL, TN 37825	Date: 5/18/23	Scale: N/A
Product Designer: HARVILLEED	M46068	
32X68		DWV
		M46068




APPROVED ERWG APPROVED
12 JUN 2023
Federal Manufactured Home Construction And Safety Standards

GILES HOMES Model #: MODEL# Drawing #:
405 S. BROAD ST., NEW TAZEWEll, TN 37825 Date: 5/18/23 Scale: N/A M46068
Product Designer: HARVILLEED Product Size: 32X68

ELEC SUB

M46068



APPROVED BY
HARVILLE HOME CONSTRUCTION
12 JUN 2023
Federal Manufactured Home Construction And Safety Standards


GILES HOMES	Model #: MODEL#	Drawing #:
405 S. BROAD ST., NEW TAZEWELL, TN 37825	Date: 5/18/23	Scale: N/A
Product Designer: HARVILLE	32X68	
FLOOR PLAN SUB		M46068

LEGEND		APPLIANCE	BTU's	RATINGS	MAX. INPUT
SYM	FITTINGS				
A	TEE	FURNACE	77,000	BTU'S	
B	90 ELL	W/H	36,000	BTU'S	
X	VALVE	RANGE	56,000	BTU'S	
C	CAP				

MDL = 40'

NOTES:

- 1) ALL PIPE IS 3/4" I.D.CAST
(EXCEPT WHERE NOTED OTHERWISE)
- 2) MDL=MAX. DETERMINED LENGTH OF PIPE
- 3) FITTING MAY BE ADDED OR SUBTRACTED
TO TRAVERSE VARIATIONS IN AXLE
QUANTITY, PLACEMENT, AND FRAME TYPE.
- 4) INLET LOCATION MAY VARY TO STAY WITHIN
MAX. DETERMINED LENGTH



APPROVED **HWG A** APPROVED
12 JUN 2023


Federal Manufactured
Home Construction
And Safety Standards

3

GILES HOMES	Model #: MODEL#	Drawing #:
405 S. BROAD ST. NEW TAZEWELL, TN 37825	Date: 5/18/23	Scale: N/A
Product Designer: HARVILLEED	M46068	
GAS LINES		M46068

HOT
Cold

Unless noted all lines 1/2"



APPROVED IRVING APPROVED
12 JUN 2023
Federal Manufactured
Home Construction
And Safety Standards

GILES HOMES	Model #: MODEL#	Drawing #:
405 S. BROAD ST. NEW TAZEWELL, TN 37825	Date: 5/18/23	Scale: N/A
Product Designer: HARVILLEED	32X68	
PRESSURE LINES		M46068

Model # M46068**Giles Homes Light and Vent Chart**

Room	Floor Area SQFT	Window(s)	Glass Area	% of Floor	Artificial Light	Vent Area	% of Floor	Artificial Vent	Min. Door
Living Room	253	3660 x2	24.4	9.64%		12.4	4.90%		Vent
Kitchen	210	3040	6.3	3.00%	X	3.3	1.57%	X	36
DINING	142	3660	12.2	8.59%		6.2	4.37%		24
P-BEDROOM	154	3060 x2	19.8	12.86%		10.4	6.75%		28
DEN	190	3060 x2	19.8	10.42%		10.4	5.47%		36
Bedroom 2	132	3660	12.2	9.24%		6.2	4.70%		24
Bedroom 3	132	3660	12.2	9.24%		6.2	4.70%		24
Bedroom 4	132	3660	12.2	9.24%		6.2	4.70%		24
P- Bath	125	3640	10.48	8.38%	X	0	0.00%	X	24
Bath 2	52	0			X			X	24
					X			X	
Utility	65	0							24

* (X) Artificial Light and Vent has been provided for this room

** Note: All window sizes are minimum requirements for rooms. And windows may be added as long as heat loss allows and/or is documented on the floor plan

APPROVED BY: HWC A APPROVED

12 JUN 2023





Federal Manufactured
Home Construction
And Safety Standards

3


Data on this submitted

By: Andy Cupp

MFG. Giles Industries



*THIS FOOTER DIAGRAM IS FOR STANDARD PRODUCT ONLY
*FOR PIER SPACING REFER TO SET UP MANUAL





Manual S Compliance Report

Entire House

Clayton Homes

Job: M46068-FDJ-TZIII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZIII, GILES

HRWG

APPROVED

12 JUN 2023

3

Federal Manufactured
Home Construction
And Safety Standards

APPROVED

Cooling Equipment

Design Conditions

Outdoor design DB:	87.6°F	Sensible gain:	13047	Btuh	Entering coil DB:	75.0°F
Outdoor design WB:	71.2°F	Latent gain:	3210	Btuh	Entering coil WB:	62.2°F
Indoor design DB:	75.0°F	Total gain:	16256	Btuh		
Indoor RH:	50%	Estimated airflow:	593	cfm		

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Split AC	Model:	R4A518GKB+FED002410++NADA43601CK
Manufacturer:	Smart Comfort		
Actual airflow:	593 cfm		
Sensible capacity:	19121 Btuh	147% of load	
Latent capacity:	2428 Btuh	76% of load	
Total capacity:	21549 Btuh	133% of load	SHR: 89%

Heating Equipment

Design Conditions

Outdoor design DB:	15.8°F	Heat loss:	21859	Btuh	Entering coil DB:	70.0°F
Indoor design DB:	70.0°F					

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Elec strip	Model:	
Manufacturer:	Smart Comfort		
Actual airflow:	593 cfm		
Output capacity:	0 kW	0% of load	Temp. rise: 0 °F

Meets all requirements of ACCA Manual S.



wrightsoft®
A MiTek® / Berkshire Hathaway Company

Right-Suite® Universal 2023 23.0.01 RSU28322

...GilesEngine050508\2021-MODELS\3268\Project2.rup Calc = MJ8 Front Door faces: N

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

For: M46068-FDJ-TZIII, GILES

12 JUN 2023

 APPROVED
 APPROVED
Federal Manufactured
Home Construction
And Safety Standards**Design Conditions**
Location:
 VA-SG22
 Elevation: 2133 ft
 Latitude: 37°N

Outdoor:
 Dry bulb (°F) 16
 Daily range (°F) -
 Wet bulb (°F) -
 Wind speed (mph) 15.0


Heating **Cooling**
 88
 20 (M)
 71
 7.5

Indoor:
 Indoor temperature (°F) 70
 Design TD (°F) 54
 Relative humidity (%) 50
 Moisture difference (gr/lb) 48.7


Infiltration:
 Method Simplified
 Construction quality Average
 Fireplaces 0

Heating **Cooling**
 75
 13
 50
 28.1
Heating

Component	Btuh/ft ²	Btuh	% of load
Walls	4.1	5503	25.2
Glazing	19.0	2964	13.6
Doors	17.3	728	3.3
Ceilings	1.7	3346	15.3
Floors	1.2	2428	11.1
Infiltration	3.6	5566	25.5
Ducts		0	0
Piping		0	0
Humidification		0	0
Ventilation		1324	6.1
Adjustments		0	0
Total		21859	100.0

**Cooling**

Component	Btuh/ft ²	Btuh	% of load
Walls	1.4	1960	15.0
Glazing	13.2	2056	15.8
Doors	7.8	327	2.5
Ceilings	1.5	2951	22.6
Floors	0	0	0
Infiltration	0.4	681	5.2
Ducts		0	0
Ventilation		923	7.1
Internal gains		4150	31.8
Blower		0	0
Adjustments		0	0
Total		13047	100.0



Latent Cooling Load = 3210 Btuh

Overall U-value = 0.058 Btuh/ft²-°F, Window / Floor Area = 7.8 %

Data entries checked.



Component Constructions

Entire House

Clayton Homes

Job: M46068-FDJ-TZIII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZIII, GILES

12 JUN 2023

APPROVED **APPROVED**

Federal Manufactured Home Construction And Safety Standards

3

Design Conditions

Location:

VA-SG22
 Elevation: 2133 ft
 Latitude: 37°N

Outdoor:

	Heating	Cooling
Dry bulb (°F)	16	88
Daily range (°F)	-	20 (M)
Wet bulb (°F)	-	71
Wind speed (mph)	15.0	7.5

Indoor:

Indoor temperature (°F)	70	75
Design TD (°F)	54	13
Relative humidity (%)	50	50
Moisture difference (gr/lb)	48.7	28.1

Infiltration:

Method	Simplified
Construction quality	Average
Fireplaces	0

Heating

Cooling

Construction descriptions

Walls

R-15 SIDEWALL: R-15-SIDEWALL-R-15-THP-504

Or	Area ft ²	U-value Btuh/ft ² °F	Insul R ft ² ·°F/Btu	Htg HTM Btuh/ft ²	Loss Btuh	Cdg HTM Btuh/ft ²	Gain Btuh
n	462	0.075	15.0	4.07	1879	1.45	669
e	236	0.075	15.0	4.07	959	1.45	342
s	419	0.075	15.0	4.07	1705	1.45	607
w	236	0.075	15.0	4.07	959	1.45	342
all	1354	0.075	15.0	4.07	5503	1.45	1960

Partitions

(none)

Windows

Clayton - Thermopane Low-E: Clayton - Thermopane Low-E; 50% blinds 45°, medium; 50% outdoor insect screen; 6.67 ft head ht

n	57	0.350	0	19.0	1075	7.76	440
s	100	0.350	0	19.0	1889	11.8	1175
all	156	0.350	0	19.0	2964	10.3	1615

Doors

CMH - Standard Door: CMH - Standard Door - Solid no storm

n	21	0.320	0	17.3	364	7.78	163
s	21	0.320	0	17.3	364	7.78	163
all	42	0.320	0	17.3	728	7.78	327

Ceilings

DW -158 R-38

1991	0.031	38.0	1.68	3346	1.48	2951
------	-------	------	------	------	------	------

Floors

SW-180-R-22: DW-180-R-22-THP-164

1991	0.045	22.0	1.22	2428	0	0
------	-------	------	------	------	---	---



A MMiTek® / Berkshire Hathaway Company

Right-Suite@Universal 2023 23.0.01 RSU28322

...GilesEngine0505082021-MODELS132681Project2.rup Calc = MJ8 Front Door faces: N

2023-Jun-12 12:14:45

Page 1



Project Summary

Entire House

Clayton Homes

Job: M46068-FDJ-TZIII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZIII, GILES

Notes: DUCT CAPACITY-19766 BTUHS

IRWG

APPROVED

12 JUN 2023

3

Federal Manufactured
Home Construction
And Safety Standards

Design Information

Weather: VA-SG22

Winter Design Conditions

Outside db	16 °F
Inside db	70 °F
Design TD	54 °F

Summer Design Conditions

Outside db	88 °F
Inside db	75 °F
Design TD	13 °F
Daily range	M
Relative humidity	50 %
Moisture difference	28 gr/lb

Heating Summary

Structure	21859 Btuh
Ducts	0 Btuh
Central vent (0 cfm) (none)	0 Btuh
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	21859 Btuh

Sensible Cooling Equipment Load Sizing

Structure	13047 Btuh
Ducts	0 Btuh
Central vent (0 cfm) (none)	0 Btuh
Blower	0 Btuh
Use manufacturer's data	n
Rate/swing multiplier	0.93
Equipment sensible load	12081 Btuh

Infiltration

Method	Simplified Average	
Construction quality	0	
Fireplaces	0	
Area (ft ²)	Heating	Cooling
Volume (ft ³)	1991	1991
Air changes/hour	15930	15930
Equiv. AVF (cfm)	0.38	0.20
	101	53

Latent Cooling Equipment Load Sizing

Structure	3210 Btuh
Ducts	0 Btuh
Central vent (0 cfm) (none)	0 Btuh
Equipment latent load	3210 Btuh
Equipment Total Load (Sen+Lat)	15291 Btuh
Req. total capacity at 0.70 SHR	1.4 ton

Heating Equipment Summary

Make	Smart Comfort
Trade	
Model	
AHRI ref	
Efficiency	100 EFF
Heating input	0 kW
Heating output	0 Btuh
Temperature rise	0 °F
Actual air flow	593 cfm
Air flow factor	0.027 cfm/Btuh
Static pressure	0.30 in H2O
Space thermostat	

Cooling Equipment Summary

Make	Smart Comfort
Trade	SMART COMFORT
Cond	R4A518GKB
Coil	FED002410++NADA43601CK
AHRI ref	203358045
Efficiency	12.2 EER, 14 SEER
Sensible cooling	12460 Btuh
Latent cooling	5340 Btuh
Total cooling	17800 Btuh
Actual air flow	593 cfm
Air flow factor	0.045 cfm/Btuh
Static pressure	0.30 in H2O
Load sensible heat ratio	0.80

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Right-Suite® Universal 2023 23.0.01 RSU28322

...GilesEngine0505082021-MODELS\3268\Project2.rup Calc = MJ8 Front Door faces: N



Duct System Summary

Entire House

Clayton Homes

Job: M46068-FDJ-TZIII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZIII, GILES

12 JUN 2023

APPROVED

IRWG

APPROVED

Federal Manufactured
Home Construction
And Safety Standards

	Heating	Cooling
External static pressure	0.30 in H ₂ O	0.30 in H ₂ O
Pressure losses	0 in H ₂ O	0 in H ₂ O
Available static pressure	0.30 in H ₂ O	0.30 in H ₂ O
Supply / return available pressure	0.150 / 0.150 in H ₂ O	0.150 / 0.150 in H ₂ O
Lowest friction rate	0.191 in/100ft	0.191 in/100ft
Actual air flow	593 cfm	593 cfm
Total effective length (TEL)		157 ft

Supply Branch Detail Table

Name	Design (Btu/h)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
BATH	h 568	15	9	0.194	5.0	0x0	VIFx	54.4	100.0	st5
BEDROOM 2	c 841	35	38	0.229	5.0	0x0	VIFx	30.9	100.0	st5
BEDROOM 3	c 817	34	37	0.201	5.0	0x0	VIFx	48.9	100.0	st5
BEDROOM 4	h 2144	58	47	0.191	5.0	0x0	VIFx	56.9	100.0	st5
DEN	c 3128	140	142	0.723	6.0	0x0	VIFx	6.5	35.0	st1
DINING	h 1323	36	22	0.465	5.0	0x0	VIFx	29.5	35.0	st3
KITCHEN	c 2008	62	91	0.632	5.0	0x0	VIFx	12.5	35.0	st3
LIVING ROOM	c 2125	69	97	0.222	6.0	0x0	VIFx	35.4	100.0	st4
P-BATH	h 2613	71	38	0.417	5.0	0x0	VIFx	37.0	35.0	st3
PRIMARY BEDROOM	h 2706	73	71	0.217	6.0	0x0	VIFx	37.9	100.0	st4

Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Duct Material	Trunk
st4	PeakAVF	142	168	0.217	346	5.3	5 x 14	ShtMetl	st2
st1	PeakAVF	140	142	0.723	293	4.5	5 x 14	ShtMetl	
st3	PeakAVF	168	151	0.417	347	4.3	5 x 14	ShtMetl	
st5	PeakAVF	143	132	0.191	343	3.0	5 x 12	ShtMetl	
st2	PeakAVF	285	300	0.191	720	3.0	5 x 12	MetlFlx	st2

Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb1	0x0	593	593	0	0	0	0	0x0		VIFx	

APPROVED IRWC APPROVED
12 JUN 2023
3
Federal Manufactured Home Construction And Safety Standards



Manual S Compliance Report

Entire House

Clayton Homes

Job: M46068-FDJ-TZII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZII, GILES

ERWGE

A APPROVED

12 JUN 2023

3

Federal Manufactured
Home Construction
And Safety Standards

Cooling Equipment

Design Conditions

Outdoor design DB:	92.6°F	Sensible gain:	14845	Btuh	Entering coil DB:	75.0°F
Outdoor design WB:	74.3°F	Latent gain:	3974	Btuh	Entering coil WB:	62.4°F
Indoor design DB:	75.0°F	Total gain:	18818	Btuh		
Indoor RH:	50%	Estimated airflow:	767	cfm		

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Split AC	Model:	R4A324GKH+FED002410++NADA43601CK
Manufacturer:	Smart Comfort		
Actual airflow:	767 cfm		
Sensible capacity:	19121 Btuh	129% of load	
Latent capacity:	2428 Btuh	61% of load	
Total capacity:	21549 Btuh	115% of load	SHR: 89%

Heating Equipment

Design Conditions

Outdoor design DB:	15.0°F	Heat loss:	22482	Btuh	Entering coil DB:	70.0°F
Indoor design DB:	70.0°F					

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Elec strip	Model:	
Manufacturer:	Smart Comfort		
Actual airflow:	767 cfm		
Output capacity:	0 kW	0% of load	Temp. rise: 0 °F

Meets all requirements of ACCA Manual S.



wrightsoft®
A MiTek® / Berkshire Hathaway Company

Right-Suite® Universal 2023 23.0.01 RSU28322

...GilesEngine050508\2021-MODELS\3268\Project2.rup Calc = MJ8 Front Door faces: N

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZII, GILES

IHC APPROVED
 12 JUN 2023
 Federal Manufactured
Home Construction
And Safety Standards

Design Conditions

Location:
 Knoxville McGhee Tyson AP, TN, US
 Elevation: 981 ft
 Latitude: 36°N

Outdoor:	Heating	Cooling
Dry bulb (°F)	15	93
Daily range (°F)	-	19 (M)
Wet bulb (°F)	-	74
Wind speed (mph)	15.0	7.5

Indoor:
 Indoor temperature (°F)
 Design TD (°F)
 Relative humidity (%)
 Moisture difference (gr/lb)


Heating	Cooling
70	75
55	18
50	50
47.0	36.2

Infiltration:
 Method
 Construction quality
 Fireplaces

Simplified
Average
0


Heating

Component	Btuh/ft ²	Btuh	% of load
Walls	4.1	5584	24.8
Glazing	19.3	3008	13.4
Doors	17.6	739	3.3
Ceilings	1.7	3395	15.1
Floors	1.2	2464	11.0
Infiltration	3.8	5891	26.2
Ducts		0	0
Piping		0	0
Humidification		0	0
Ventilation		1401	6.2
Adjustments		0	0
Total		22482	100.0



Cooling

Component	Btuh/ft ²	Btuh	% of load
Walls	1.9	2513	16.9
Glazing	13.8	2158	14.5
Doors	9.5	400	2.7
Ceilings	1.7	3287	22.1
Floors	0	0	0
Infiltration	0.6	992	6.7
Ducts		0	0
Ventilation		1345	9.1
Internal gains		4150	28.0
Blower		0	0
Adjustments		0	0
Total		14845	100.0



Latent Cooling Load = 3974 Btuh
 Overall U-value = 0.058 Btuh/ft²·°F, Window / Floor Area = 7.8 %

Data entries checked.



Component Constructions

Entire House

Clayton Homes

Job: M46068-FDJ-TZII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZII, GILES

APPROVED **APPROVED**

12 JUN 2023

Federal Manufactured Home Construction And Safety Standards

3

Design Conditions

Location:

Knoxville McGhee Tyson AP, TN, US

Elevation: 981 ft

Latitude: 36°N

Outdoor:

Dry bulb (°F) 15

Daily range (°F) -

Wet bulb (°F) -

Wind speed (mph) 15.0

Heating

Cooling

Indoor:

Indoor temperature (°F)

Heating

Cooling

70

75

55

18

50

50

47.0

36.2

Infiltration:

Method

Construction quality

Fireplaces

Simplified

Average

0

Construction descriptions

Walls

R-15 SIDEWALL: R-15-SIDEWALL-R-15-THP-504

Or	Area ft ²	U-value Btu/h/ft ² °F	Insul R ft ² ·°F/Btu/h	Htg HTM Btu/h/ft ²	Loss Btu/h	Cdg HTM Btu/h/ft ²	Gain Btu/h
n	462	0.075	15.0	4.13	1907	1.86	858
e	236	0.075	15.0	4.13	974	1.86	438
s	419	0.075	15.0	4.13	1730	1.86	779
w	236	0.075	15.0	4.13	974	1.86	438
all	1354	0.075	15.0	4.13	5584	1.86	2513

Partitions

(none)

Windows

Clayton - Thermopane Low-E: Clayton - Thermopane Low-E; 50% blinds 45°, medium; 50% outdoor insect screen; 6.67 ft head ht

n	57	0.350	0	19.3	1091	9.39	532
s	100	0.350	0	19.3	1917	13.0	1295
all	156	0.350	0	19.3	3008	11.7	1826

Doors

CMH - Standard Door: CMH - Standard Door - Solid no storm

n	21	0.320	0	17.6	370	9.52	200
s	21	0.320	0	17.6	370	9.52	200
all	42	0.320	0	17.6	739	9.52	400

Ceilings

DW -158 R-38

1991	0.031	38.0	1.70	3395	1.65	3287
------	-------	------	------	------	------	------

Floors

SW-180-R-22: DW-180-R-22-THP-164

1991	0.045	22.0	1.24	2464	0	0
------	-------	------	------	------	---	---



Right-Suite@Universal 2023 23.0.01 RSU28322

...GilesEngine0505082021-MODELS132681Project2.rup Calc = MJ8 Front Door faces: N

2023-Jun-12 12:16:07

Page 1



Project Summary

Entire House

Clayton Homes

Job: M46068-FDJ-TZII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZII, GILES

Notes: DUCT CAPACITY-19766 BTUHS

12 JUN 2023

3

APPROVED

RWG

APPROVED

Federal Manufactured
Home Construction
And Safety Standards

Design Information

Weather: Knoxville McGhee Tyson AP, TN, US

Winter Design Conditions

Outside db	15 °F
Inside db	70 °F
Design TD	55 °F

Outside db	93 °F
Inside db	75 °F
Design TD	18 °F
Daily range	M
Relative humidity	50 %
Moisture difference	36 gr/lb

Summer Design Conditions

Structure	22482 Btuh
Ducts	0 Btuh
Central vent (0 cfm) (none)	0 Btuh
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	22482 Btuh

Sensible Cooling Equipment Load Sizing

Structure	14845 Btuh
Ducts	0 Btuh
Central vent (0 cfm) (none)	0 Btuh
Blower	0 Btuh
Use manufacturer's data	n
Rate/swing multiplier	0.98
Equipment sensible load	14488 Btuh

Infiltration

Method	Simplified	
Construction quality	Average	
Fireplaces	0	
Area (ft ²)	Heating	Cooling
Volume (ft ³)	1991	1991
Air changes/hour	15930	15930
Equiv. AVF (cfm)	0.38	0.20
	101	53

Latent Cooling Equipment Load Sizing

Structure	3974 Btuh
Ducts	0 Btuh
Central vent (0 cfm) (none)	0 Btuh
Equipment latent load	3974 Btuh
Equipment Total Load (Sen+Lat)	18462 Btuh
Req. total capacity at 0.70 SHR	1.7 ton

Heating Equipment Summary

Make	Smart Comfort
Trade	
Model	
AHRI ref	
Efficiency	100 EFF
Heating input	0 kW
Heating output	0 Btuh
Temperature rise	0 °F
Actual air flow	767 cfm
Air flow factor	0.034 cfm/Btuh
Static pressure	0.30 in H2O
Space thermostat	

Cooling Equipment Summary

Make	Smart Comfort
Trade	SMART COMFORT
Cond	R4A324GKH
Coil	FED002410++NADA43601CK
AHRI ref	203358027
Efficiency	11.5 EER, 13 SEER
Sensible cooling	16100 Btuh
Latent cooling	6900 Btuh
Total cooling	23000 Btuh
Actual air flow	767 cfm
Air flow factor	0.052 cfm/Btuh
Static pressure	0.30 in H2O
Load sensible heat ratio	0.79

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Right-Suite® Universal 2023 23.0.01 RSU28322

...GilesEngine0505082021-MODELS\3268\Project2.rup Calc = MJ8 Front Door faces: N



Duct System Summary

Entire House

Clayton Homes

Job: M46068-FDJ-TZII
 Date: May 31, 2023
 By:

5000 Clayton Road, Maryville, TN 37804 Phone: 865-380-3000

Project Information

For: M46068-FDJ-TZII, GILES

12 JUN 2023

APPROVED

IRWG

APPROVED

Federal Manufactured
Home Construction
And Safety Standards

	Heating	Cooling
External static pressure	0.30 in H ₂ O	0.30 in H ₂ O
Pressure losses	0 in H ₂ O	0 in H ₂ O
Available static pressure	0.30 in H ₂ O	0.30 in H ₂ O
Supply / return available pressure	0.150 / 0.150 in H ₂ O	0.150 / 0.150 in H ₂ O
Lowest friction rate	0.191 in/100ft	0.191 in/100ft
Actual air flow	767 cfm	767 cfm
Total effective length (TEL)		157 ft

Supply Branch Detail Table

Name	Design (Btu/h)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
BATH	h 583	20	12	0.194	5.0	0x0	VIFx	54.4	100.0	st5
BEDROOM 2	c 916	46	47	0.229	5.0	0x0	VIFx	30.9	100.0	st5
BEDROOM 3	c 888	44	46	0.201	5.0	0x0	VIFx	48.9	100.0	st5
BEDROOM 4	h 2206	75	61	0.191	6.0	0x0	VIFx	56.9	100.0	st5
DEN	c 3831	182	198	0.723	7.0	0x0	VIFx	6.5	35.0	st1
DINING	h 1356	46	30	0.465	5.0	0x0	VIFx	29.5	35.0	st3
KITCHEN	c 2166	79	112	0.632	5.0	0x0	VIFx	12.5	35.0	st3
LIVING ROOM	c 2277	88	118	0.222	7.0	0x0	VIFx	35.4	100.0	st4
P-BATH	h 2689	92	53	0.417	5.0	0x0	VIFx	37.0	35.0	st3
PRIMARY BEDROOM	h 2781	95	90	0.217	6.0	0x0	VIFx	37.9	100.0	st4

Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Duct Material	Trunk
st4	PeakAVF	183	207	0.217	427	5.3	5 x 14	ShtMetl	st2
st1	PeakAVF	182	198	0.723	407	4.5	5 x 14	ShtMetl	
st3	PeakAVF	217	195	0.417	447	4.3	5 x 14	ShtMetl	
st5	PeakAVF	184	167	0.191	443	3.0	5 x 12	ShtMetl	
st2	PeakAVF	368	374	0.191	898	3.0	5 x 12	MetlFlx	st2

Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb1	0x0	767	767	0	0	0	0	0x 0		VIFx	

REV C
APPROVED 12 JUN 2023
APPROVED 3
Federal Manufactured Home Construction And Safety Standards